



检验报告

TEST REPORT

中心编号(No.): 201704AW108



样品名称: 轻集料连锁砌块

Sample Name

委托单位: 北京东方光耀新型建材有限公司

Client

Test Type

人人及技术

(国家)建筑材料工业技术监督研究中心

建筑材料工业干混砂浆产品质量监督检验测试中心 China Building Material Industry Center for Quality Supervision and Test of Dry-mixed Mortar





(国家)建筑材料工业技术监督研究中心

建筑材料工业干混砂浆产品质量监督检验测试中心

China Building Material Industry Center for Quality Supervision and Test of Dry-mixed Mortar

检验报告

TEST REPORT

中心编号(No.): 201704AW108

第1页共2页

			77 1 7 1 7 7					
样品名称	轻集补连锁砌块	检验类别	委托检验 7					
委托单位	北京东方光耀新型建材有限公司	商标						
生产单位	北京东方光耀新型建材有限公司	等 级	MU3.5					
生产日期		样品编号						
来样日期	2017年04月01日	规格型号	395mm×195mm×190mm					
样品数量	32块	样品状态	块状 一口 1					
检验依据	GB/T 15229-2011《轻集料混凝土小型空心砌块》 GB 6566-2010《建筑材料放射性核素限量》							
检验项目			4. 抗压强度 效射性比活度)					
检验结论	*经检验,送检样品的尺寸偏。检验结果符合标准 GB/T 15229-201 果符合标准 GB/T 15229-2011 中密强度的检验结果符合标准 GB/T 152 要求;放射性(放射性比活度)的类装饰装修材料的技术指标要求,	1 的技术指标。 度等级 1000 : 29-2011 中强度 检验结果符合	要求:密度等级的检验结 级的技术指标要求:抗压 建等级 MU3.5 的技术指标 标准 GB6566-2010 中 A					

备注:(此处空白)

批准: 4:

制、书、图 编

检验单位地址。北京市朝阳区管庄中国建材院内北楼

电话: 010-51164723

邮编: 100024



(国家)建筑材料工业技术监督研究中心

建筑材料工业干混砂浆产品质量监督检验测试中心

China Building Material Industry Center for Quality Supervision and Test of Dry-mixed Mortar

检验报告

TEST REPORT

中心编号(No.): 201704AW108

第2页共2页

						7777 777		
序号	检验项目			标准要求		检验结果		单项 结论
超	尺寸	1000000000000000000000000000000000000		att.		2~+2		合格
513	偏差					0 ~ +2 -2 ~ +2		合格
克克	/mm							合格
認	外质	最小外壁 厚/mm	用于非		20	22		合格
路		肋厚mm	承重墙体	\$30×	20	22505		合格
2		缺棱	个数/块	12 P.	\$2	4226-2226		合格
			三个方向投影 的最大值/mm		20	经验银		合格
		裂缝延伸的累计尺寸 /mm			30	3200		合格
	密度等級/ (kg/m³) (密度等级 1000 级)			≥910 ,	≤1000	960		合格
	抗压强度/MPa (强度等级 MU3.5)		平均值	最小值	平均值	最小值	合格	
22			≥3.5	≥2.8	3.6	3.4		
5	吸水率/%			130 €180		25		合格
6	相对含水率(中等湿度地区)/%			35 €35		29		合格
	放射性 (放射性比活度) (A 类)		内照射指数 (I _{Ra}) ≤1.0		0.2		合格	
			外服射指数 (iy) ≤1.3		0.3		合格	

备注:(此处空白)

检验单位地址: 北京市朝阳区管庄中国建材院内北楼

说明

Notice

- 1、本报告无中心"检验测试章"和骑缝章无效。 This test report is invalid without the seal.
- 本报告无"编制、审核、批准"签字无效。
 This test report is invalid without the signatures of the related persons.
- 3、本报告涂改、部分复印无效。

This test report is invalid if erased, altered or copied partially.

4、对本报告若有异议,应于收到报告之日起十五个工作日内向本中心提出,逾 期恕不受理。

Any doubt should inform us within 15 workdays after receiving the test report.

5、委托检验样品和委托信息由委托人提供,中心不对真实性负责,委托检验结果仅对来样负责。

The commissioned testing samples and commission information are provided by the applicant. The results shown in the test report refer only to the sample(s) tested unless otherwise stated. Identifying authenticity of the supplied samples and information is out of our responsibility.

6、本报告的法律责任由建筑材料工业技术监督研究中心承担。

The legal responsibility of this test report is charged with Technical Supervision and Research Center of the Building Materials Industry.

7、本报告采用防伪纸张,复印后应带有网络底纹。

This test report is printed on anti-counterfeiting paper. Its copy should have grid shading.

本中心联系方式:

地址(Address): 北京市朝阳区管庄东里一号北楼

No.1 Guanzhuang Dongli, Chaoyang District, Beijing 100024, P.R. China.

邮编 (Post Code): 100024

电话 (Tel): (010) 51164723 51164718

传真 (Fax): (010) 51164724

报告真伪查询 (Tel): (010) 51164716

网址 (Web): http://www.dmtc.org.cn/

电子邮箱 (E-mail): dmtc2007@163.com